



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

1 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Permanent Testing				
1	CHEMICAL- BUILDING MATERIAL	ADMIXTURE	Ash Content	IS 9103 (RA - 2018)
2	CHEMICAL- BUILDING MATERIAL	ADMIXTURE	Chloride Content	IS 6925 : (RA - 2018)
3	CHEMICAL- BUILDING MATERIAL	ADMIXTURE	Dry Material Content	IS 9103 (RA - 2018)
4	CHEMICAL- BUILDING MATERIAL	ADMIXTURE	pH	IS 9103 (RA - 2018)
5	CHEMICAL- BUILDING MATERIAL	ADMIXTURE	Relative Density	IS 9103 (RA - 2018)
6	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Alkali Aggregate Reactivity - Dissolved Silica	IS 2386 (Part-7) (RA - 2021)
7	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Alkali Aggregate Reactivity - Reduction in Alkalinity	IS 2386 (Part-7) (RA - 2021)
8	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Chloride	EN 1744-1
9	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Organic Impurities	IS 2386 (Part-2) (RA - 2021)
10	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Soundness	IS 2386 (Part-5) (RA - 2021)
11	CHEMICAL- BUILDING MATERIAL	Coarse Aggregate	Sulphates	EN 1744-1
12	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Alkali Aggregate Reactivity - Dissolved Silica	IS 2386 : (Part - 7) (RA - 2021)
13	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Alkali Aggregate Reactivity - Reduction in Alkalinity	IS 2386 : (Part - 7) (RA - 2021)
14	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Chloride	EN 1744 - 1
15	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Organic Impurities	IS 2386 : (Part - 2) (RA - 2021)
16	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Soundness	IS 2386 : (Part - 5) (RA - 2021)
17	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Sulphates	EN 1744 - 1
18	CHEMICAL- BUILDING MATERIAL	Fly Ash	Available Alkalies - Potassium Oxide (K ₂ O)	IS 3812 (Part-1) (RA - 2022)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

2 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
19	CHEMICAL- BUILDING MATERIAL	Fly Ash	Available Alkalies - Sodium Oxide (Na ₂ O)	IS 3812 (Part-1) (RA - 2022)
20	CHEMICAL- BUILDING MATERIAL	Fly Ash	CaO Content	IS 1727 (RA - 2018)
21	CHEMICAL- BUILDING MATERIAL	Fly Ash	Chloride	IS 4032 (RA - 2019)
22	CHEMICAL- BUILDING MATERIAL	Fly Ash	Combined Oxides R ₂ O ₃ (Fe ₂ O ₃ + Al ₂ O ₃)	IS 1727 (RA - 2018)
23	CHEMICAL- BUILDING MATERIAL	Fly Ash	Loss on Ignition	IS 1727 (RA - 2018)
24	CHEMICAL- BUILDING MATERIAL	Fly Ash	Magnesia (MgO)	IS 1727 (RA - 2018)
25	CHEMICAL- BUILDING MATERIAL	Fly Ash	Silica Content (SiO ₂)	IS 1727 (RA - 2018)
26	CHEMICAL- BUILDING MATERIAL	Fly Ash	Silicon dioxide + Aluminum Oxide + Ferric Oxide	IS 1727 (RA - 2018)
27	CHEMICAL- BUILDING MATERIAL	Fly Ash	Sulphuric Anhydride (SO ₃)	IS 1727 (RA - 2018)
28	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace	Alumina (Al ₂ O ₃)	IS 4032 (RA - 2019)
29	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Insoluble Residue	IS 4032 (RA - 2019)
30	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Iron Oxide (Fe ₂ O ₃)	IS 4032 (RA - 2019)
31	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Lime (CaO)	IS 4032 (RA - 2019)
32	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Loss on Ignition	IS: 4032 : (RA - 2019)
33	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Magnesia (MgO)	IS 4032 (RA - 2019)
34	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Manganese Oxide	IS 4032 (RA - 2019)
35	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Silica Content (SiO ₂)	IS 4032 (RA - 2019)
36	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag	Sulphide Sulphur	IS 4032 (RA - 2019)
37	CHEMICAL- BUILDING MATERIAL	HARDENED CONCRETE / MORTAR	Chloride	IS 14959 (Part-2) : 2001



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

3 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
38	CHEMICAL- BUILDING MATERIAL	HARDENED CONCRETE / MORTAR	pH	IS 2720 (Part-26) : 1987
39	CHEMICAL- BUILDING MATERIAL	HARDENED CONCRETE / MORTAR	Sulphates	BS: 1881 (Part-124)
40	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Aluminum Oxide	IS 4032 (RA - 2019)
41	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Available Alkalies - Sodium Oxide (Na ₂ O)	IS 4032 (RA - 2019)
42	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Available Alkalies - Potassium Oxide (K ₂ O)	IS 4032 (RA - 2019)
43	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Calcium oxide Content	IS 4032 (RA - 2019)
44	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Chloride	IS 4032 (RA - 2019)
45	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Ferric Oxide	IS 4032 (RA - 2019)
46	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Insoluble Residue	IS 4032 (RA - 2019)
47	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Loss on Ignition	IS 4032 (RA - 2019)
48	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Magnesia (MgO)	IS 4032 (RA - 2019)
49	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Silica Content as SiO ₂	IS 4032 (RA - 2019)
50	CHEMICAL- BUILDING MATERIAL	OPC 33, 43 & 53 Grade	Sulphuric Anhydride (SO ₃)	IS 4032 (RA - 2019)
51	CHEMICAL- BUILDING MATERIAL	PPC	Chloride	IS 4032 (RA - 2019)
52	CHEMICAL- BUILDING MATERIAL	PPC	Insoluble Residue	IS 4032 (RA - 2019)
53	CHEMICAL- BUILDING MATERIAL	PPC	Loss on Ignition	IS 4032 (RA - 2019)
54	CHEMICAL- BUILDING MATERIAL	PPC	Magnesia (MgO)	IS 4032 (RA - 2019)
55	CHEMICAL- BUILDING MATERIAL	PPC	Sulphuric Anhydride (SO ₃)	IS 4032 (RA - 2019)
56	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Aluminium	IS 8811 : (RA 2018)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

4 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
57	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Carbon	IS 8811 (RA 2018)
58	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Chromium	IS 8811 (RA - 2018)
59	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Copper	IS 8811 : (RA 2018)
60	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Manganese	IS 8811 : (RA 2018)
61	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Molybdenum	IS 8811 : (RA 2018)
62	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Nickel	IS 8811 : (RA 2018)
63	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Phosphorus	IS 8811 : (RA 2018)
64	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Silicon	IS 8811 : (RA 2018)
65	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Sulphur	IS 8811 : (RA 2018)
66	CHEMICAL- METALS & ALLOYS	Ferrous Materials Base - Low Alloy Steel	Vanadium	IS 8811 : (RA - 2018)
67	CHEMICAL- WATER	Water for construction purpose	Chloride Content as CL	IS 3025 (Part 32) (RA 2019)
68	CHEMICAL- WATER	Water for construction purpose	Inorganic Solids(Fixed Residue)	IS 3025 (Part 18)
69	CHEMICAL- WATER	Water for construction purpose	Organic Solids (Volatile Residue)	IS 3025 (Part 18)
70	CHEMICAL- WATER	Water for construction purpose	pH	IS 3025 (Part 11)
71	CHEMICAL- WATER	Water for construction purpose	Sulphate content as SO ₃	IS 3025 (Part 24) (Sec 1)
72	CHEMICAL- WATER	Water for construction purpose	Total Suspended Solids	IS 3025 (Part 17)
73	CHEMICAL- WATER	Water for construction purpose	Volume of 0.02N H ₂ SO ₄ to neutralize 100ml of sample (Alkalinity)	IS 3025 (Part 23)
74	CHEMICAL- WATER	Water for construction purpose	Volume of 0.02N NaOH to neutralize 100 ml of sample (Acidity)	IS 3025 (Part 22) RA 2019
75	MECHANICAL- BUILDINGS MATERIALS	AUTOCLAVED AREATED CONCRETE BLOCKS	BLOCK DENSITY	IS 6441 (PART 1) (RA 2022)
76	MECHANICAL- BUILDINGS MATERIALS	AUTOCLAVED AREATED CONCRETE BLOCKS	COMPRESSIVE STRENGTH	IS 6441 (PART 5) (RA 2022)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

5 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
77	MECHANICAL- BUILDINGS MATERIALS	BITUMEN EMULSION	COAGULATION OF EMULSION	IS 8887
78	MECHANICAL- BUILDINGS MATERIALS	BITUMEN EMULSION	MISCIBILITY WITH WATER	IS 8887
79	MECHANICAL- BUILDINGS MATERIALS	BITUMEN EMULSION	RESIDUE BY EVAPORATION	IS 8887
80	MECHANICAL- BUILDINGS MATERIALS	BITUMEN EMULSION	RESIDUE ON 600 MICRONS	IS 8887
81	MECHANICAL- BUILDINGS MATERIALS	BITUMINOUS MIX	BINDER CONTENT	ASTM D 2172/ D2172M
82	MECHANICAL- BUILDINGS MATERIALS	BITUMINOUS MIX	DENSITY	ASTM D 2726
83	MECHANICAL- BUILDINGS MATERIALS	BITUMINOUS MIX	MARSHAL STABILITY	ASTM D 6927
84	MECHANICAL- BUILDINGS MATERIALS	BRICKS	COMPRESSIVE STRENGTH	IS 3495 (PART 1)
85	MECHANICAL- BUILDINGS MATERIALS	BRICKS	EFFLORESCENCE	IS 3495 (PART 3)
86	MECHANICAL- BUILDINGS MATERIALS	BRICKS	WATER ABSORPTION	IS 3495 (PART 2)
87	MECHANICAL- BUILDINGS MATERIALS	BURNT CLAY HOLLOW BRICKS AND BLOCKS	COMPRESSIVE STRENGTH	IS 3952 (ANNEXURE A)
88	MECHANICAL- BUILDINGS MATERIALS	BURNT CLAY HOLLOW BRICKS AND BLOCKS	WATER ABSORPTION	IS 3952 (ANNEXURE B)
89	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	10 % FINE'S VALUE	IS:2386 (Part 4) (RA 2021)
90	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	BULK DENSITY (LOOSE)	IS:2386 (Part 3) (RA 2021)
91	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	BULK DENSITY (RODDED)	IS:2386 (Part 3) (RA 2021)
92	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	CRUSHING VALUE	IS:2386 (Part 4) (RA 2021)
93	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	ELONGATION INDEX	IS 2386 (PART 1)(RA 2021)
94	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	FLAKINESS INDEX	IS 2386 (PART 1)(RA 2021)
95	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	IMPACT VALUE	IS 2386 (PART 4)(RA 2021)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

6 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
96	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	LOS ANGELES ABRASION VALUE	IS 2386 (PART 4)(RA 2021)
97	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	MATERIAL FINER THAN 75 MICRONS	IS 2386 (PART 1)(RA 2021)
98	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	SIEVE ANALYSIS	IS 2386 (PART 1)(RA 2021)
99	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	SPECIFIC GRAVITY	IS 2386 (PART 3)(RA 2021)
100	MECHANICAL- BUILDINGS MATERIALS	COARSE AGGREGATE	WATER ABSORPTION	IS 2386 (PART 3)(RA 2021)
101	MECHANICAL- BUILDINGS MATERIALS	CONCRETE BEAMS	FLEXURAL STRENGTH	IS 516 (Part 1/ Sec. 1)
102	MECHANICAL- BUILDINGS MATERIALS	CONCRETE CORES	COMPRESSIVE STRENGTH	IS 516 (PART 4)
103	MECHANICAL- BUILDINGS MATERIALS	CONCRETE CUBES	COMPRESSIVE STRENGTH	IS 516 (Part 1/ Sec. 1)
104	MECHANICAL- BUILDINGS MATERIALS	CONCRETE CYLINDERS	MODULUS OF ELASTICITY	IS 516 : Part 8 : Sec 1
105	MECHANICAL- BUILDINGS MATERIALS	CONCRETE CYLINDERS	SPLITTING TENSILE STRENGTH	IS 516 (Part 1/ Sec. 1)
106	MECHANICAL- BUILDINGS MATERIALS	CONCRETE MIX	CONSISTENCY	IS 1199 PART 2
107	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	BULK DENSITY (LOOSE)	IS 2386 (PART 3)(RA 2021)
108	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	BULK DENSITY (RODDED)	IS 2386 (PART 3)(RA 2021)
109	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	BULKING	IS 2386 (PART 3)(RA 2021)
110	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	MATERIAL FINER THAN 75 MICRONS	IS 2386 (PART 1)(RA 2021)
111	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	SIEVE ANALYSIS	IS 2386 (PART 1)(RA 2021)
112	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	SPECIFIC GRAVITY	IS 2386 (PART 3)(RA 2021)
113	MECHANICAL- BUILDINGS MATERIALS	FINE AGGREGATE	WATER ABSORPTION	IS 2386 (PART 3)(RA 2021)
114	MECHANICAL- BUILDINGS MATERIALS	HOLLOW / SOLID CONCRETE BLOCKS	BLOCK DENSITY	IS 2185 (PART 1) Annexure E



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

7 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
115	MECHANICAL- BUILDINGS MATERIALS	HOLLOW / SOLID CONCRETE BLOCKS	COMPRESSIVE STRENGTH	IS 2185 (PART 1) Annexure D
116	MECHANICAL- BUILDINGS MATERIALS	HOLLOW / SOLID CONCRETE BLOCKS	DIMENSIONAL ANALYSIS (Length, Width and Height)	IS 2185 (Part 1) Annex. B
117	MECHANICAL- BUILDINGS MATERIALS	HOLLOW / SOLID CONCRETE BLOCKS	WATER ABSORPTION	IS 2185 (PART 1)
118	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	COMPRESSIVE STRENGTH	IS 4031 (PART 6)
119	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	CONSISTENCY	IS 4031 (PART 4)
120	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	DENSITY	IS 4031 (PART 11)
121	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	FINAL SETTING TIME	IS 4031 (PART 5)
122	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	FINENESS (BLAINE'S METHOD)	IS 4031 (PART 2)
123	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	INITIAL SETTING TIME	IS 4031 (PART 5)
124	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	SOUNDNESS (By Autoclave method)	IS 4031 (PART 3)
125	MECHANICAL- BUILDINGS MATERIALS	HYDRAULIC CEMENT	SOUNDNESS (By Le-Chatelier method)	IS 4031 (PART 3)
126	MECHANICAL- BUILDINGS MATERIALS	PAVER BLOCKS	COMPRESSIVE STRENGTH	IS 15658
127	MECHANICAL- BUILDINGS MATERIALS	PAVER BLOCKS	WATER ABSORPTION	IS 15658
128	MECHANICAL- BUILDINGS MATERIALS	POZZOLANA-FLY ASH, SILICA FUME, GGBS, ALCCOFINE	SPECIFIC GRAVITY	IS 1727
129	MECHANICAL- BUILDINGS MATERIALS	POZZOLANA-FLYASH, GGBS	FINENESS (BLAINE'S METHOD)	IS 1727
130	MECHANICAL- BUILDINGS MATERIALS	POZZOLANA-FLYASH, SILICA FUME, ALCCOFINE, GGBS	RESIDUE ON 45 MICRON SIEVE	IS 1727
131	MECHANICAL- BUILDINGS MATERIALS	SELF COMPACTING CONCRETE MIX	FLOW TEST	IS 1199 PART 6
132	MECHANICAL- BUILDINGS MATERIALS	SELF COMPACTING CONCRETE MIX	V FUNNEL	IS 1199 PART 6



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

8 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
133	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	KINEMATIC VISCOSITY @ 135°C and 150 °C	IS 1206 (Part 3)
134	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	LOSS ON HEATING	IS 1212
135	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	Specific Gravity	IS 1202
136	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	ABSOLUTE VISCOSITY @ 60°C	IS 1206 (PART 2)
137	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	DUCTILITY	IS 1208 : Part 1
138	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	ELASTIC RECOVERY	IS 1208 : Part 2
139	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	FLASH POINT	IS 1209
140	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	MATTER SOLUBLE IN TCE	IS 1216
141	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	PENETRATION	IS 1203
142	MECHANICAL- BUILDINGS MATERIALS	VISCOSITY GRADE BITUMEN, CRUMB RUBBER MODIFIED BITUMEN, POLYMER MODIFIED BITUMEN, NATURAL RUBBER MODIFIED BITUMEN	SOFTENING POINT	IS 1205
143	MECHANICAL- MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	0.2 % PROOF STRESS	IS 1608 (Part 1)
144	MECHANICAL- MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	BEND TEST	IS 1599
145	MECHANICAL- MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	ELONGATION	IS 1608 (Part 1)
146	MECHANICAL- MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	MASS / METER	IS 1786



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

9 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
147	MECHANICAL-MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	RE-BEND TEST	IS 1786
148	MECHANICAL-MECHANICAL PROPERTIES OF METALS	HIGH STRENGTH DEFORMED STEEL BARS AND WIRES FOR CONCRETE REINFORCEMENT	TENSILE STRENGTH	IS 1608 (Part 1)
149	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STEEL TUBES	ELONGATION	IS 1608 (Part 1)
150	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STEEL TUBES	MASS PER METER RUN	IS 1239 / IS 1161
151	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STEEL TUBES	TENSILE STRENGTH	IS 1608 (Part 1)
152	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STEEL TUBES	YIELD STRESS	IS 1608 (Part 1)
153	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STRUCTURAL STEEL	BEND TEST	IS 1599
154	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STRUCTURAL STEEL	ELONGATION	IS 1608 (Part 1)
155	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STRUCTURAL STEEL	TENSILE STRENGTH	IS 1608 (Part 1)
156	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STRUCTURAL STEEL	WEIGHT / METER	IS 808
157	MECHANICAL-MECHANICAL PROPERTIES OF METALS	STRUCTURAL STEEL	YIELD STRESS	IS 1608 (Part 1)
158	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	0.2 % PROOF LOAD	IS 14268
159	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	BREAKING LOAD	IS 14268
160	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	Elongation	IS 14268



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

10 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
161	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	Lay Length	IS 14268
162	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	NOMINAL AREA	IS 14268
163	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Uncoated Stress Relieved Low Relaxation 7-ply Strand for Prestressed concrete	UNIT WEIGHT	IS 14268
164	MECHANICAL- SOIL AND ROCK	NATURAL BUILDING STONE	TRUE SPECIFIC GRAVITY	IS 1122
165	MECHANICAL- SOIL AND ROCK	NATURAL BUILDING STONE	UNIAXIAL COMPRESSIVE STRENGTH	IS 1121 (PART 1)
166	MECHANICAL- SOIL AND ROCK	NATURAL BUILDING STONE	WATER ABSORPTION	IS 1124
167	MECHANICAL- SOIL AND ROCK	ROCK	DENSITY	IS 13030
168	MECHANICAL- SOIL AND ROCK	ROCK	UNCONFINED COMPRESSIVE STRENGTH	IS 9143
169	MECHANICAL- SOIL AND ROCK	ROCK	WATER CONTENT	IS 13030
170	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	FREE SWELL INDEX	IS 2720 (PART 40) (RA:2021)
171	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	LIGHT COMPACTION (MDD)	IS 2720 (PART 7)(RA:2021)
172	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	LIGHT COMPACTION (OMC)	IS 2720 (PART 7)(RA:2021)
173	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	MOISTURE CONTENT	IS 2720 (PART 2)
174	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	SPECIFIC GRAVITY	IS 2720 (PART 3 / SECTION 1) (RA:2021)
175	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	CALIFORNIA BEARING RATIO (CBR)	IS 2720 (PART 16) (RA:2021)
176	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	GRAIN SIZE ANALYSIS	IS 2720 (PART 4)
177	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	HEAVY COMPACTION (MDD)	IS 2720 (PART 8)
178	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	HEAVY COMPACTION (OMC)	IS 2720 (PART 8)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

11 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
179	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	LIQUID LIMIT	IS 2720 (PART 5)
180	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	PARTICLE SIZE ANALYSIS (By Hydrometer method)	IS 2720 (PART 4)
181	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM/BLANKET	PLASTIC LIMIT	IS 2720 (PART 5)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

STEDRANT TECHNOCLINIC PRIVATE LIMITED (CONSTRUCTION MATERIALS TESTING LABORATORY), SHED NO. F-3/A, ROAD NO.10, IDA NACHARAM, HYDERABAD, TELANGANA, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-7523

Page No

12 of 12

Validity

04/07/2024 to 03/07/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Site Testing				
1	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	FIELD DENSITY (By Core Cutter method)	IS 2720 (PART 29)
2	MECHANICAL- SOIL AND ROCK	SOIL / GRANULAR SUB BASE / WET MIX MACADAM	FIELD DENSITY (By Sand Replacement Method)	IS 2720 (PART 28)
3	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Carbonation	BS EN 14630
4	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Cover Meter	BS 1881 (Part 204)
5	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Deflection Measurement Data (Load Test)	IS 456, Clause 17.6
6	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Half-Cell Potential Difference	ASTM C 876
7	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Rebound Hammer	IS 13311 (Part 2)
8	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structures	Ultrasonic Pulse Velocity	IS 516 (Part 5 / Sec 1)